

Stagemobil XXL

 =  1-2 hours



Introduction

The Stagemobil XXL offers 61 m² of stage floor.

A team of qualified riggers can easily have this stage set up in 1-2 hours.

Stage floor

Width x Depth	10.0m x 6.1m
Surface	61m ²
Floor height	≈ 1.1m – 1.3m
Resistance	300kg/m ²

Roof

Width x Depth	10.0m x 6.1m
Capacity	900kg
Clearance	4.0m – 4.6m
Optional sound wing I	2 x 270kg
Optional sound wing II	2 x 500kg

Setup

Stage technician	1 person
Stage hands	2 persons
Estimated setup	1-2 hours

Trailer

Length	11.85m
Width	2.54m
Height	3.95m
Weight	3.5t
Electrical	CEE

Add-ons and optional items

Risers
Barriers
Backdrop
Sound wing
Load-in dock
Cable defenders

Technical

